



भा.कृ.अनु.प – केंद्रीय द्वीपीय कृषि अनुसंधान संस्थान
ICAR – CENTRAL ISLAND AGRICULTURAL RESEARCH INSTITUTE
बाथूबस्ती, गाराचरमा डाकघर, श्री विजयपुरम – 744105
Bathu Basti, Garacharma P.O, Sri Vijaya Puram – 744105
Phone: 03192 – 250436; 250235
Email: hoa.ciari@nic.in, director.ciari@icar.org.in, Website: <http://ciari.res.in>

F. No. 57(20)/22-23/Estate

Date: 27.08.2026

NOTICE INVITING LIMITED TENDER

NAME OF THE WORK: Work order for construction of check dam (4.0m x 1.2m) at Bloomsdale farm.

CRITICAL DATE SHEET

Tender Reference No.	F. No. 57(20)/22-23/Estate
Estimated Amount	₹ 1,44,512/-
Last Date & Time of Tender / Bid submission	07.09.2026 at 03.00 PM
Date & Time of Tender / Bid Opening	07.09.2026 at 03:30 PM
Address of Communication	The Director, ICAR-CIARI, Sri Vijaya Puram
Place of Bid Submission	Reception, Administrative Block – II, ICAR-CIARI, Bathu Basti, Sri Vijaya Puram – 744 105
Place of Bid Opening	AO Chamber, Administrative Block – II, ICAR- CIARI, Bathu Basti, Sri Vijaya Puram – 744 105

For
27/08/26

Assistant Administrative Officer

Copy to:

1. Er. M. Arul Selvam, CTO & In-charge Estate Section, ICAR-CIARI, Sri Vijaya Puram.
2. The Incharge AKMU Cell, ICAR-CIARI, Sri Vijaya Puram for publication in Institute's Website.
3. P.S to Director, ICAR-CIARI, Sri Vijaya Puram for information of the Director please.



भा.कृ.अनु.प - केंद्रीय द्वीपीय कृषि अनुसंधान संस्थान
ICAR - CENTRAL ISLAND AGRICULTURAL RESEARCH INSTITUTE

बाथूबस्ती, गाराचरमा डाकघर, श्री विजयपुरम - 744105

Bathu Basti, Garacharma P.O, Sri Vijaya Puram - 744105

Phone: 03192 - 250436; 250235

Email: hoa.ciari@nic.in, director.ciari@icar.org.in, Website: <http://ciari.res.in>

F. No. 57(20)22-23/Estate

Date: 27.08.2026

To,

TENDER DOCUMENT

Name of Work: Work order for construction of check dam (4.0m x 1.2m) at Bloomsdale farm.

Sl. No.	Description of items	Qty	Unit	Rate Per Unit	Amount (in Rs.)
1.	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge. All kinds of soil	7.30	cum		
2.	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	5.15	cum		
3.	Laying of temporary PVC pipe from the temporary earthen dam to allow water to pass through the ongoing RCC check dam work including removing of the PVC pipe after completion of the construction work.	20.00	metre		
4.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
4.1	1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	1.35	cum		
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
5.1	Thermo-Mechanically Treated bars of grade Fe-500D or more.	250.00	kg		
6.	Centering and shuttering including strutting, propping etc. and removal of form for				
6.1	Foundations, footings, bases of columns, etc. for mass concrete	1.60	Sqm		
6.2	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	14.50	Sqm		

	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level .:				
7.1	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	3.10	cum		
8.	12 mm cement plaster of mix :				
8.1	1:4 (1 cement: 4 fine sand)	24.00	Sqm		
9.	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.(Fabrication of GI channel using GI angle 30x20x5 and 40x40x6)	27.50	kg		
10.	Providing in single piece 30mm thick plain WPC board and cutting it to required size including providing and fixing rubber gasket (12 cm x 3mm) on three edges (bottom and 2 vertical) with required SS screws at a spacing of 15cm c/c on both sides and inserting it in the GI-channel section to function as check dam gate shutter, all complete as per the direction of I/c Estate Section.	1.0	Sqm		
11.	Finishing walls with Acrylic Smooth exterior paint of required shade : 13.46.1 New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	14.00	Sqm		
Total					

TERMS & CONDITIONS:

- 1) The envelope containing tender and other documents should be neatly superscribed with the name of the work, reference no., closing date failing which the tender will be returned without opening.
- 2) The contractor should mention the correct postal address and contact no. in the space provided in the agreement. If there is any change in the postal address/ contact no., the contractor should inform to the office in writing immediately about the change. Institute shall not be responsible for non-receipt of document due to postal delay/ undelivered/ non-recipient at your end.
- 3) The contractor may quote the rate after inspection of site and clarification of all details of the tender document from the In-charge Estate Section, ICAR-CIARI, Sri Vijaya Puram.
- 4) Incomplete or conditional quotations shall be rejected.
- 5) Work shall be carried out as per the instruction, direction and satisfaction of In-charge Estate Section, ICAR-CIARI, Sri Vijaya Puram.
- 6) The rate should be inclusive of all taxes.
- 7) The rate should also include all labours and material charges, transportation, tools and tackles etc. as required for completing the work.
- 8) The work should be started within 07 (Seven) days from the date of issue of work order failing which the work order shall be cancelled on the recommendation of the In-charge Estate Section, ICAR-CIARI, Sri Vijaya Puram and performance guarantee deposited will be forfeited by the Institute.
- 9) The work should be completed within 45 (Forty Five) days from the date of issue of work order failing which the work order shall be cancelled on the recommendation of the In-charge Estate Section, ICAR-CIARI, Sri Vijaya Puram and performance guarantee deposited will be forfeited by the Institute.
- 10) Liquidated Damages: For repair works costing up to ₹ 5 lakh – 0.5% of the contract value per week of delay subject to a maximum of 10% of the contract value.
- 11) The Director shall have the liberty to postpone or not to execute any item of work and the contractor shall not be entitled to any compensation for non-execution of such items of work.

- During execution no change shall be made by the contractor in the approved specifications at site without the consent of the In-charge Estate Section, ICAR-CIARI, Sri Vijaya Puram.
- 13) All the materials purchased for construction/repair/painting etc. by the contractor shall be as per the CPWD/ ISI/ BIS Standards/ specification and got approved by the Engineer-In-charge.
 - 14) The inferior quality or rejected materials are to be removed immediately from the site failing which the same will get removed by the Institute and the expense involved will be deducted from the contractor's bill.
 - 15) The water as required for construction and curing shall be arranged by the contractor for which no extra payment shall be made.
 - 16) The contractor shall not be provided any store for storing of the construction materials and their tools. However, a site will be given temporarily to construct a store in CIARI Complex. The store should be dismantled immediately after handing over the structure/ buildings to the Institute failing which the bill will not be processed for release of payment.
 - 17) In case of dis-satisfactory work the contract may be terminated at any time and in such case the security deposit shall be forfeited.
 - 18) In case the contractor fails to complete the work within the stipulated/ extended period of time and according to our satisfaction, the Director, ICAR-Central Island Agricultural Research Institute shall have the right to terminate the contract and get the work done through any other firm or agency. In such case the security deposit of the Contractor shall be forfeited.
 - 19) Quantity of work may be increased or decreased according to the actual need of work and hence minor deviation of work shall be undertaken as per quoted rate without asking any compensation.
 - 20) The contractor has to deposit 3% of the contract value through Demand Draft/FDR in favour of "ICAR Unit, CARI, Sri Vijaya Puram" as Performance Guarantee for the contract against acceptance of tender and the same shall be kept as security deposit and shall be released after one year of successful completion of the work.
 - 21) If the contractor fails to deposit 3% performance Security within 02 (Two) days (excluding holiday) from the date of issue of our letter/ e-mail communication, the tender may be cancelled and their enlistment in our Institute will be cancelled without any notice.
 - 22) The contractor has to pay minimum wages to their labour force engaged for the civil work as per A&N Administration notification issued from time to time. The contractor shall be bound by all provisions of contract labour (Regulation and Abolition) Act 1970 and Central Rules 1971.
 - 23) The standard deduction such as Income Tax and other taxes as applicable shall be deducted from the bill of the contractor.
 - 24) After completion of the work within one year, if any defect, or damage or poor workmanship is noticed, the same shall be rectified by the contractor within 10 days failing which the security deposit shall be forfeited.
 - 25) After completion of work, the left over material at the site, if any, shall be removed within seven days failing which the material shall be removed at the cost and risk of the contractor by the Institute.
 - 26) The Director, ICAR-CIARI, Sri Vijaya Puram also reserves the right to cancel the work, after award of work due to some administrative/ technical reasons.
 - 27) The Director, ICAR-CIARI, Sri Vijaya Puram shall be the sole arbitrator for all disputes between the contractor and Institute. The decision of the Director shall be final and binding to both the parties.

Ray
27/08/26

सहायक प्रशासनिक अधिकारी
Assistant Administrative Office

For 27-08-26

Signature of the Contractor
Name & Complete Postal Address
With Telephone No., Date and Seal.