



भा.कृ.अनु.प – केंद्रीय द्वीपीय कृषि अनुसंधान संस्थान
ICAR – CENTRAL ISLAND AGRICULTURAL RESEARCH INSTITUTE
बाथूबस्ती, गाराचरमा डाकघर, श्री विजयपुरम – 744105
Bathu Basti, Garacharma P.O, Sri Vijaya Puram – 744105
Phone: 03192 – 250436; 250235
Email: hoa.ciari@nic.in, director.ciari@icar.org.in, Website: <http://ciari.res.in>

फा. सं. F. No. 57(58)/2017-18/Estate

दिनांक/Date: 12.06.2026

सीमित निविदा सूचना
NOTICE INVITING LIMITED TENDER

कार्य का नाम: मत्स्य विज्ञान प्रभाग, गाराचरमा फार्म हेतु तालाब के पास ओवरहेड जल टंकी (जी.आई. ट्यूबुलर फ्रेमवर्क) का निर्माण।
आकार: 2.5 मीटर (लंबाई) × 2.5 मीटर (चौड़ाई) × 3 मीटर (ऊँचाई)

NAME OF THE WORK: C/o overhead water tank (GI tubular framework) near pond for Fisheries Science Division at Garacharma Farm.
Size: 2.5 m (L) X 2.5 m (B) X 3m (H)

महत्वपूर्ण तारीख तालिका
CRITICAL DATE SHEET

निविदा संदर्भ संख्या Tender Reference No.	F. No. 57(58)/2017-18/Estate
अनुमानित राशि / Estimated Amount	₹ 1,41,488/-
निविदा/बोली जमा करने की अंतिम तिथि एवं समय Last Date & Time of Tender / Bid submission	19.06.2025 at 03.00 PM
निविदा/बोली खोलने की तिथि एवं समय Date & Time of Tender / Bid Opening	19.06.2025 at 03:30 PM
संपर्क के लिए पता Address of Communication	The Director, ICAR-CIARI, Sri Vijaya Puram
बोली जमा करने का स्थान Place of Bid Submission	स्वागत कक्ष, प्रशासनिक ब्लॉक-ए, भा.कृ.अनु.प.-के.द्वी.कृ.अनु. सं, भातू बस्ती, श्री विजयपुरम – 744 105 Reception, Administrative Block – II, ICAR-CIARI, Bathu Basthi, Sri Vijaya Puram – 744 105
बोली खोलने का स्थान Place of Bid Opening	प्रशासनिक अधिकारी का कक्ष, प्रशासनिक ब्लॉक-III भा.कृ. अनु.प.-के.द्वी.कृ.अनु.सं, भातू बस्ती, श्री विजयपुरम – 744 105 AO Chamber, Administrative Block – II, ICAR-CIARI, Bathu Basthi, Sri Vijaya Puram – 744 105

(Signature)
Asst. Administrative Officer
(Sridham Kumar Biswas)
Central Island Agricultural Research Institute
Port Blair
Assistant Administrative Officer

प्रतिलिपी/ Copy to:

1. Er. M. Arul Selvam, CTO & In-charge Estate Section, ICAR-CIARI, Sri Vijaya Puram.
2. The Incharge AKMU Cell, ICAR-CIARI, Sri Vijaya Puram for publication in Institute's Website.
3. P.S to Director, ICAR-CIARI, Sri Vijaya Puram for information of the Director please.

ICAR – CENTRAL ISLAND AGRICULTURAL RESEARCH INSTITUTE
SRI VIJAYA PURAM – 744 105

F. No. 57(58)/2017-18/Estate

Date: 12.06.2026

To

.....

TENDER DOCUMENT

कार्य का नाम:

मत्स्य विज्ञान प्रभाग, गाराचरमा फार्म हेतु तालाब के पास ओवरहेड जल टंकी
 (जी.आई. ट्यूबुलर फ्रेमवर्क) का निर्माण।
 आकार: 2.5 मीटर (लंबाई) × 2.5 मीटर (चौड़ाई) × 3 मीटर (ऊँचाई)

NAME OF THE WORK:

C/o overhead water tank (GI tubular framework) near pond for
 Fisheries Science Division at Garacharma Farm.
 Size: 2.5 m (L) X 2.5 m (B) X 3m (H)


S.No	Description of item	Qty.	Unit	Rate	Amount
	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
1	All kinds of soil	0.55	cum		
	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in- Charge:				
2	All kinds of soil	6.25	sqm		
	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:				
3	1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 20 mm nominal size derived from natural sources)	0.10	cum		
4	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	0.50	cum		
	Supplying of medium duty GI pipe (ISI marked) of approved quality and make of the sizes;				
5	25 mm dia	120.00	metre		
6	40 mm dia	65.00	metre		
7	50 mm dia	15.00	metre		
8	Labour charges for fabrication of steel framework with GI pipes for PVC tank raised platform including cutting, hoisting, fixing in position including welding and bolted with special shaped washers etc. complete.	600.00	kg		

9	Providing and fixing aluminium plain sheets of 22 guage of approved make. The sheet shall be fixed using self drilling /self tapping screws of size with EPDM seal, complete in horizontal surfaces and including cutting to size and shape wherever required.	13.00	kg		
10	Placing on terrace (at all floor levels) polyethylene water storage tank, and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	1.00	Job		
11	Providing and fixing of 40 mm dia unplasticised Polyvinyl Chloride (uPVC) pipes on externally exposed work, and all uPVC plain & brass threaded fittings including jointing of pipes & fittings with uPVC solvent cement and testing of joints complete as per direction of Engineer inCharge.	15.00	metre		
12	Providing and fixing of 50 mm dia unplasticised Polyvinyl Chloride (uPVC) pipes on externally exposed work, and all uPVC plain & brass threaded fittings including jointing of pipes & fittings with uPVC solvent cement and testing of joints complete as per direction of Engineer inCharge.	6.00	metre		
Total					₹
(Rupees					only)

TERMS & CONDITIONS:

- 1) The envelope containing tender and other documents should be neatly superscribed with the name of the work, reference no., closing date failing which the tender will be returned without opening.
- 2) The contractor should mention the correct postal address and contact no. in the space provided in the agreement. If there is any change in the postal address/ contact no., the contractor should inform to the office in writing immediately about the change. Institute shall not be responsible for non-receipt of document due to postal delay/ undelivered/ non-recipient at your end.
- 3) The contractor may quote the rate after inspection of site and clarification of all details of the tender document from the In-charge Estate Section, ICAR-CIARI, Sri Vijaya Puram.
- 4) Incomplete or conditional quotations shall be rejected.
- 5) Work shall be carried out as per the instruction, direction and satisfaction of In-charge Estate Section, ICAR-CIARI, Sri Vijaya Puram.
- 6) The rate should be inclusive of all taxes.
- 7) The rate should also include all labours and material charges, transportation, tools and tackles etc. as required for completing the work.
- 8) The work should be started within 07 (Seven) days from the date of issue of work order failing which the work order shall be cancelled on the recommendation of the In-charge Estate Section, ICAR-CIARI, Sri Vijaya Puram and performance guarantee deposited will be forfeited by the Institute.
- 9) The work should be completed within 20 (Twenty) days from the date of issue of work order failing which the work order shall be cancelled on the recommendation of the In-charge Estate Section, ICAR-CIARI, Sri Vijaya Puram and performance guarantee deposited will be forfeited by the Institute.
- 10) Liquidated Damages: For repair works costing up to ₹ 5 lakh – 0.5% of the contract value per week of delay subject to a maximum of 10% of the contract value.
- 11) The Director shall have the liberty to postpone or not to execute any item of work and the contractor shall not be entitled to any compensation for non-execution of such items of work.
- 12) During execution no change shall be made by the contractor in the approved specifications at site without the consent of the In-charge Estate Section, ICAR-CIARI, Sri Vijaya Puram.
- 13) All the materials purchased for construction/repair/painting etc. by the contractor shall be as per the CPWD/ ISI/ BIS Standards/ specification and got approved by the Engineer-In-charge.

- 14) The inferior quality or rejected materials are to be removed immediately from the site failing which the same will get removed by the Institute and the expense involved will be deducted from the contractor's bill.
- 15) The water as required for construction and curing shall be arranged by the contractor for which no extra payment shall be made.
- 16) The contractor shall not be provided any store for storing of the construction materials and their tools. However, a site will be given temporarily to construct a store in CIARI Complex. The store should be dismantled immediately after handing over the structure/ buildings to the Institute failing which the bill will not be processed for release of payment.
- 17) In case of dis-satisfactory work the contract may be terminated at any time and in such case the security deposit shall be forfeited.
- 18) In case the contractor fails to complete the work within the stipulated/ extended period of time and according to our satisfaction, the Director, ICAR-Central Island Agricultural Research Institute shall have the right to terminate the contract and get the work done through any other firm or agency. In such case the security deposit of the Contractor shall be forfeited.
- 19) Quantity of work may be increased or decreased according to the actual need of work and hence minor deviation of work shall be undertaken as per quoted rate without asking any compensation.
- 20) The contractor has to deposit 3% of the contract value through Demand Draft/FDR in favour of "ICAR Unit, CARI, Sri Vijaya Puram" as Performance Guarantee for the contract against acceptance of tender and the same shall be kept as security deposit and shall be released after one year of successful completion of the work.
- 21) If the contractor fails to deposit 3% performance Security within 02 (Two) days (excluding holiday) from the date of issue of our letter/ e-mail communication, the tender may be cancelled and their enlistment in our Institute will be cancelled without any notice.
- 22) The contractor has to pay minimum wages to their labour force engaged for the civil work as per A&N Administration notification issued from time to time. The contractor shall be bound by all provisions of contract labour (Regulation and Abolition) Act 1970 and Central Rules 1971.
- 23) The standard deduction such as Income Tax and other taxes as applicable shall be deducted from the bill of the contractor.
- 24) After completion of the work within one year, if any defect, or damage or poor workmanship is noticed, the same shall be rectified by the contractor, within 10 days failing which the security deposit shall be forfeited.
- 25) After completion of work, the left over material at the site, if any, shall be removed within seven days failing which the material shall be removed at the cost and risk of the contractor by the Institute.
- 26) The Director, ICAR-CIARI, Sri Vijaya Puram also reserves the right to cancel the work, after award of work due to some administrative/ technical reasons.
- 27) The Director, ICAR-CIARI, Sri Vijaya Puram shall be the sole arbitrator for all disputes between the contractor and Institute. The decision of the Director shall be final and binding to both the parties.


 (श्रीधाम कुमार बिस्वास)
 Asst. Administrative Officer
 Central Island Agricultural Research Institute
 Fort Bazar, Sri Vijaya Puram
 Assistant Administrative Officer

Signature of the Contractor
 Name & Complete Postal Address
 With Telephone No., Date and Seal.